

TANANA CHIEFS CONFERENCE REQUEST FOR QUOTES FOR
Fencing
Badger Road

ADDENDUM NUMBER ONE (1)

March 12, 2024

The following corrections, changes, additions, deletions, revisions, and /or clarifications are hereby made a part of the request for quotes for Fencing on 2605 Badger Rd. North Pole Alaska.

Firms providing a quote will acknowledge receipt of this addendum via email to Cortnie Doan at the following; cortnie.doan@tananachiefs.org

Final quotes to be emails to cortnie.doan@tananachiefs.org

AD1-1 Question; Will the property line be cleared prior to the fence installation? Or is the contractor responsible for clearing associated with the fence work?

AD1-1 Reply; Yes, the property line will be cleared this spring by another contractor

AD1-2 Question; The SOW references "gates". How many gates are to be included? Associated sizes?

AD1-2 Reply; One

AD1-3 Question; The site pictures and the drawing shows only 1 double gate. How wide is this gate supposed to be?


AD1-3 Reply; 16' wide double gate should be fine

AD1-4 Question; Who is responsible for clearing the vegetation. Currently, there is significant vegetation along portions where the fence is drawn.

AD1-4 Reply; TCC has a contractor already for clearing the vegetation, where the fencing will be and will be completed spring 2024.

AD1-5 Question; The SOW, section 3. P, appears to state that the fence contractor is supposed to be responsible to determine the borough requirements for easements on the property. Is this correct? It seems that survey, to mark property corners and to derive the exact location of fenceline/s, should be the responsibility of the owner. Please clarify what is expected of the contractor, in this regard.

AD1-5 Reply; Contractor will call dig safe, TCC will establish the corners and flag




AD1-6 Question; SOW section 3. J. calls for gate posts to be driven to 5'. Depending on the width of the gate/s, this is not advisable for long term durability and functionality of the gate. Is this what is required, or should the gate posts be concrete set?

AD1-6 Reply; Concrete set is probably ok but we'll want them to be wrap but are also open to what a contractor recommendation are for long term durability.

AD1-7 Question; Section 3. F. States that posts will be 11' long to allow for a 5ft burial depth. Section 3.J. states that all posts may be driven to 5', or until refusal. Please verify that the expectation is that posts will be driven to a maximum depth of 5'.

AD1-7 Reply; 5' burial depth



Tanana
Chiefs
Conference

122 First Ave
Fairbanks, AK 99701
907-452-8251
