

# HUGHES CITY HEALTH CLINIC FREEZE DAMAGE RFQ ADDENDUM #1

FEBRUARY 27, 2024

Addendum #1 identifies two additional line items for the project that will not be covered by the pending insurance claim. The line items will be priced out separately for consideration of a decision by the TCC Project Manager to follow through on.

1. A two foot by two foot access panel will be cut into the utilduct to allow access to the utilduct zone valve. The access panel will be constructed in the same manner and of the same materials as the existing utilduct. The access panel will be weather tight. The location of the access panel will be coordinated with TCC field staff.
2. The section of Arctic Pipe shown in Hughes 3 will be removed from the transition at the utilduct to five feet below grade. A new section of Arctic pipe in the same configuration as the existing section but with electric heat tape will be installed. The heat tape will be connected to the existing electric panels in the clinic. The identified electrical switch for the heat tape will be located in the clinic mechanical room.