REPAIR FREEZE DAMAGE AT THE HUGHES CITY CLINIC RFQ ADDENDUM #2

April 11, 2024

- 1. The Contractor will provide temporary repairs to the structural member identified in Addendum #2 Appendix as detailed below.
- 2. The identified damaged structural member will be re positioned in its original location.
- 3. The repair will be made using two (2) $\frac{1}{2}$ " steel plates. The steel plates will be located on opposite sides of the vertical face of the damaged beam.
- 4. The plates will then be through bolted to the existing damaged structural member.
- 5. The plates will be a minimum of 75% of the length of the beam.
- 6. The Contractor will provide and install a new wooden structural member of the same size and type as existing.
- 7. The contractor will level the clinic within 1" of level along both axis.

