



Tanana
Chiefs
Conference

ATTACHMENT A
FORT YUKON, AK - RABBIT LINE SUBVISION

April 11, 2025
BILL OF MATERIALS
Project(s):
EPS #: 25-0053
TANANA CHIEFS CONFERENCE



Status	Assembly Unit	Description	RABBIT LINE BID QUANTITY	PV DIST BID QUANTITY	Total Units	Unit of Meas.	Labor (P.U.)	Total Labor	Material (P.U.)	Total Material	Total Labor & Material
--------	---------------	-------------	--------------------------------	----------------------------	----------------	---------------------	-----------------	----------------	--------------------	-------------------	------------------------------

INSTALL											
I	#2 ACSR	#2 ACSR "SPARATE" 7/1 PRIMARY COND. (FEET)	18056	500	18556	FT	\$ -	\$ -	\$ -	\$ -	\$ -
I	35/5	35 FOOT CLASS 5 POLE	2	1	3	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	40/4	40 FOOT CLASS 4 POLE	44	2	46	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	A1.1	1PH, PRIMARY SUPPORT, TANGENT, VERTICAL	37		37	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	A5.01	1PH, PRIMARY INSULATOR ASSEMBLY	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	A5.1	1PH, PRIMARY SUPPORT, DEADEND, VERTICAL	5		5	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	A5.2	1PH, PRIMARY SUPPORT, DEADEND, VERTICAL, EXTENSION EYE BOLT	4		4	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	C1.11	3PH, PRIMARY SUPPORT, TANGENT, HORIZONTAL	6		6	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	C5.21	3PH, PRIMARY SUPPORT, DEADEND, DOUBLE 8' ARM		1	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	C5.31	3PH, PRIMARY SUPPORT, DEADEND, TRIPLE 8' ARM	3	1	4	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	C6.21	3PH, PRIMARY SUPPORT, DOUBLE DEADEND, DOUBLE 8' ARM, LOWERED NEUTRAL	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	C6.31	3PH, PRIMARY SUPPORT, DOUBLE DEADEND, TRIPLE 8' ARM, LOWERED NEUTRAL		1	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	N5.2	NEUTRAL ASSEMBLY, DEADEND, CLEVIS	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	UC1X	3PH CABLE TERMINAL POLE DEADEND, WITH CUTOUTS & ARRESTERS		1	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	R3.1	POLE MOUNTED RECLOSER, DIELECTRIC, 3 PHASE, G&W VIPER S		1	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	S1.01	CUTOUTS (SINGLE-PHASE)	5		5	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	J1.1	SEC ASSEMBLY (SMALL ANGLE), SINGLE UPSET BOLT	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	E2.02X	SINGLE OVERHEAD GUY - HEAVY DUTY 3/8" EHS	3	1	4	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	E2.1X	SINGLE DOWN GUY - HEAVY DUTY 3/8" EHS	16		16	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	E2.02X	SINGLE OVERHEAD GUY - HEAVY DUTY 3/8" EHS		1	1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	F3.18X	ANCHOR, PLATE - (18,000#)	10	2	12	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	H1.1	GROUNDING ASSEMBLY - GROUND ROD TYPE	11	3	14	EA	\$ -	\$ -	\$ -	\$ -	\$ -
I	M1.20G	CLEARING	6381		6381	FT	\$ -	\$ -	\$ -	\$ -	\$ -
INSTALL								\$ -		\$ -	\$ -

RETIRE											
R	#4 ACSR	#4 ACSR "SWANATE" 7/1 PRIMARY COND. (FEET)	917		917	FT	\$ -	\$ -	\$ -	\$ -	\$ -
R	#2 ACSR	#2 ACSR "SPARATE" 7/1 PRIMARY COND. (FEET)	723	7332	8055	FT	\$ -	\$ -	\$ -	\$ -	\$ -
R	35/5	35 FOOT CLASS 5 POLE	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	40/4	40 FOOT CLASS 4 POLE	6		6	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	40/2	40 FOOT CLASS 2 POLE		12	12	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	A1.11	1PH, PRIMARY SUPPORT, TANGENT, HORIZONTAL	5		5	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	A5.11	1PH, PRIMARY SUPPORT, DEADEND, HORIZONTAL, SINGLE 8' ARM	2		2	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	A5.21	1PH, PRIMARY SUPPORT, DEADEND, HORIZONTAL, DOUBLE 8' ARM	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	A6.21	1PH, PRIMARY SUPPORT, DOUBLE DEADEND, HORIZONTAL	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	C1.11	3PH, PRIMARY SUPPORT, TANGENT, HORIZONTAL		10	10	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	C5.21	3PH, PRIMARY SUPPORT, DEADEND, DOUBLE 8' ARM		2	2	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	UC1X	3PH CABLE TERMINAL POLE DEADEND, WITH CUTOUTS & ARRESTERS		3	3	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	S1.01	CUTOUTS (SINGLE-PHASE)	2		2	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	E1.1X	SINGLE DOWN GUY, LIGHT DUTY	10		10	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	E2.1X	SINGLE DOWN GUY - HEAVY DUTY 3/8" EHS		4	4	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	F3.18X	ANCHOR, PLATE - (18,000#)	2	4	6	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	H1.1	GROUNDING ASSEMBLY - GROUND ROD TYPE	3		3	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	UM50-P-4	CONDUIT, 4" PVC - SCHEDULE 40 (FEET)		170	170	FT	\$ -	\$ -	\$ -	\$ -	\$ -
RETIRE								\$ -		\$ -	\$ -

REMOVE & REINSTALL											
R	COMM	EXISTING COMMUNICATIONS CABLE	13		13	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	TPX	TRIPLEX (FEET)	7		7	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	G1.4-10-A	1PH OVERHEAD CONVENTIONAL TRANSFORMER (120/240V, 10 kVA)	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	G1.4-15-A	1PH OVERHEAD CONVENTIONAL TRANSFORMER (120/240V, 15 kVA)	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	G1.4-25-A	1PH OVERHEAD CONVENTIONAL TRANSFORMER (120/240V, 25 kVA)	1		1	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	J3.1	SEC ASSEMBLY, DEADEND, CLEVIS	9		9	EA	\$ -	\$ -	\$ -	\$ -	\$ -
R	ST LT	STREETLIGHT	1			EA	\$ -	\$ -	\$ -	\$ -	\$ -
REMOVE AND REINSTALL								\$ -		\$ -	\$ -

SUBTOTAL	\$ -		\$ -	\$ -
MOB/DEMOB				
TOTAL	\$ -		\$ -	\$ -