



Tanana
Chiefs
Conference

ATTACHMENT A
FORT YUKON - RABBIT LINE SUBDIVISION

May 2, 2025
BILL OF MATERIAL - REVISION 1
Project(s):
EPS #: 25-0053
OWNER #: TANANA CHIEFS CONFERENCE



Status	Assembly Unit	Description	Bid Quantity	Adjusted Const. Quantity	Unit of Meas.	Labor (P.U.)	Total Labor	Material (P.U.)	Total Material	Total Labor & Material
--------	---------------	-------------	--------------	--------------------------	---------------	--------------	-------------	-----------------	----------------	------------------------

INSTALL

I	#2 ACSR	#2 ACSR "SPARATE" 7/1 PRIMARY COND. (FEET)	18056		FT		\$ -		\$ -	\$ -
I	#2 TPX	#2 TRIPLEX	1485		FT		\$ -		\$ -	\$ -
I	35/5	35 FOOT CLASS 5 POLE	9		EA		\$ -		\$ -	\$ -
I	40/4	40 FOOT CLASS 4 POLE	44		EA		\$ -		\$ -	\$ -
I	A1.1	1PH, PRIMARY SUPPORT, TANGENT, VERTICAL	37		EA		\$ -		\$ -	\$ -
I	A5.01	1PH, PRIMARY INSULATOR ASSEMBLY	1		EA		\$ -		\$ -	\$ -
I	A5.1	1PH, PRIMARY SUPPORT, DEADEND, VERTICAL	5		EA		\$ -		\$ -	\$ -
I	A5.2	1PH, PRIMARY SUPPORT, DEADEND, VERTICAL, EXTENSION EYE BOLT	4		EA		\$ -		\$ -	\$ -
I	C1.11	3PH, PRIMARY SUPPORT, TANGENT, HORIZONTAL	6		EA		\$ -		\$ -	\$ -
I	C5.31	3PH, PRIMARY SUPPORT, DEADEND, TRIPLE 8' ARM	3		EA		\$ -		\$ -	\$ -
I	C6.21	3PH, PRIMARY SUPPORT, DOUBLE DEADEND, DOUBLE 8' ARM, LOWERED NEUTRAL	1		EA		\$ -		\$ -	\$ -
I	NS.2	NEUTRAL ASSEMBLY, DEADEND, CLEVIS	1		EA		\$ -		\$ -	\$ -
I	S1.01	CUTOUTS (SINGLE-PHASE)	5		EA		\$ -		\$ -	\$ -
I	G1.4-15-A	1PH OVERHEAD CONVENTIONAL TRANSFORMER (2400-120/240V, 15 kVA)	5		EA		\$ -		\$ -	\$ -
I	J1.1	SEC ASSEMBLY (SMALL ANGLE), SINGLE UPSET BOLT	7		EA		\$ -		\$ -	\$ -
I	J2.1	SEC ASSEMBLY (LARGE ANGLE)	1		EA		\$ -		\$ -	\$ -
I	J3.1	SEC ASSEMBLY, DEADEND, CLEVIS	7		EA		\$ -		\$ -	\$ -
I	E1.1X	SINGLE DOWN GUY, LIGHT DUTY	6		EA		\$ -		\$ -	\$ -
I	E2.02X	SINGLE OVERHEAD GUY - HEAVY DUTY 3/8" EHS	3		EA		\$ -		\$ -	\$ -
I	E2.1X	SINGLE DOWN GUY - HEAVY DUTY 3/8" EHS	16		EA		\$ -		\$ -	\$ -
I	F3.8X	ANCHOR, PLATE - (8,000#)	6		EA		\$ -		\$ -	\$ -
I	F3.18X	ANCHOR, PLATE - (18,000#)	10		EA		\$ -		\$ -	\$ -
I	H1.1	GROUNDING ASSEMBLY - GROUND ROD TYPE	15		EA		\$ -		\$ -	\$ -
I	M1.20G	CLEARING	6381		FT		\$ -		\$ -	\$ -
RABBIT LINE INSTALL							\$ -		\$ -	\$ -

RETIRE

R	#4 ACSR	#4 ACSR "SWANATE" 7/1 PRIMARY COND. (FEET)	917		FT		\$ -		\$ -	\$ -
R	#2 ACSR	#2 ACSR "SPARATE" 7/1 PRIMARY COND. (FEET)	723		FT		\$ -		\$ -	\$ -
R	35/5	35 FOOT CLASS 5 POLE	1		EA		\$ -		\$ -	\$ -
R	40/4	40 FOOT CLASS 4 POLE	6		EA		\$ -		\$ -	\$ -
R	A1.11	1PH, PRIMARY SUPPORT, TANGENT, HORIZONTAL	5		EA		\$ -		\$ -	\$ -
R	A5.11	1PH, PRIMARY SUPPORT, DEADEND, HORIZONTAL, SINGLE 8' ARM	2		EA		\$ -		\$ -	\$ -
R	A5.21	1PH, PRIMARY SUPPORT, DEADEND, HORIZONTAL, DOUBLE 8' ARM	1		EA		\$ -		\$ -	\$ -
R	A6.21	1PH, PRIMARY SUPPORT, DOUBLE DEADEND, HORIZONTAL	1		EA		\$ -		\$ -	\$ -
R	S1.01	CUTOUTS (SINGLE-PHASE)	2		EA		\$ -		\$ -	\$ -
R	E1.1X	SINGLE DOWN GUY, LIGHT DUTY	10		EA		\$ -		\$ -	\$ -
R	F3.18X	ANCHOR, PLATE - (18,000#)	2		EA		\$ -		\$ -	\$ -
R	H1.1	GROUNDING ASSEMBLY - GROUND ROD TYPE	3		EA		\$ -		\$ -	\$ -
RABBIT LINE RETIRE							\$ -		\$ -	\$ -

REMOVE & REINSTALL

RR	COMM	EXISTING COMMUNICATIONS CABLE	13		EA		\$ -		\$ -	\$ -
RR	TPX	TRIPLEX (FEET)	7		EA		\$ -		\$ -	\$ -
RR	G1.4-10-A	1PH OVERHEAD CONVENTIONAL TRANSFORMER (120/240V, 10 kVA)	1		EA		\$ -		\$ -	\$ -
RR	G1.4-15-A	1PH OVERHEAD CONVENTIONAL TRANSFORMER (120/240V, 15 kVA)	1		EA		\$ -		\$ -	\$ -
RR	G1.4-25-A	1PH OVERHEAD CONVENTIONAL TRANSFORMER (120/240V, 25 kVA)	1		EA		\$ -		\$ -	\$ -
RR	J3.1	SEC ASSEMBLY, DEADEND, CLEVIS	9		EA		\$ -		\$ -	\$ -
RR	ST LT	STREETLIGHT	1		EA		\$ -		\$ -	\$ -
RABBIT LINE REMOVE AND REINSTALL							\$ -		\$ -	\$ -

SUBTOTAL
MOBILIZATION/DEMOBILIZATION
TOTAL

\$ -		\$ -	\$ -
\$ -		\$ -	\$ -
\$ -		\$ -	\$ -